



SCHEDULE OF OPENINGS		
DETAILS	WIDTH	HEIGHT
DOORS	30"	70"
01	30"	70"
02	30"	70"
WINDOWS	40"	40"
W	40"	40"
V	20"	40"
	20"	20"

1. FOUNDATION :- AS PER DESIGN
2. F.C.C :- 1:1.25 (NORMAL MIX RATIO)
3. BRICK WALL :- 15 CM R.C.C SURFACE & 15 CM OVER BRICK SURFACE
4. PLASTERING :- 15 CM R.C.C SURFACE & 15 CM OVER BRICK SURFACE
5. FLOORING :- 15" THK L.P.S FLOOR IN 15 OVER 4" THK C.C.C IN 1:2:4
6. WOOD WORK :- SAL IN DOOR GROUNDW & FLUSH DOOR SHUTTER OF W.P. PLY
7. STEEL WORK :- STEEL FRAME IN WINDOW/SAL IN DOOR SHUTTER OF W.P. PLY
8. PAINT FINISHING :- COLOUR WASH TWO COAT OVER 10. P.O.P INSIDE & SMOKEW. OVER OUTER WALL PASTER

PROPOSED BUILDING PLAN FOR  
TECHNOLOGICAL BUILDING CENTRE PVT LTD  
JAYANTI WEST RD

**SCHEDULE OF LAND**  
 KHATA NO. : 48  
 PLOT NO. : 455  
 THANA NO. : 131  
 MOUZA : ANANCI  
 DIST. : SARANKELA KHARSAWAN

**STATEMENT OF AREA**  
 1. TOTAL PLOT AREA :- 593.85 Sq.Mt  
 2. BUILT-UP AREA :- 519.88 Sq.Mt  
 3. GROUND FLOOR BUILT UP AREA :- 86.30 Sq.Mt  
 4. FIRST FLOOR AREA :- 351.14 Sq.Mt  
 5. SECOND FLOOR AREA :- 181.14 Sq.Mt  
 6. STAIR ROOM AREA :- 48.32 Sq.Mt  
 7. % OF COVERED AREA :- 86.26 %  
 8. MACHINE PLAN :- Building Area :- 519.88 Sq.Mt  
 9. ROAD AREA :- 73.97 Sq.Mt  
 10. TOTAL :- 593.85

SIGN OF OWNER : \_\_\_\_\_ SIGN OF Engineer : \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_