



1. FOUNDATION - 75TH SAND BLIND OVER 75TH FLAT BRICK SOLING OVER 200TH P.C.C OVER R.C.C COLAR RAFT FOUNDATION.
2. SUPER STRUCTURE - 1ST CLASS BRICK WORKS IN CEMENT MORTAR.
3. D.P.C - ALL ROOMS 150L DAMP PROOF COURSE.
4. R.C.C WORK - R.C.C COLUMN BEAMS UNITE (1:1:2-4) WITH REBARS.
5. PLASTER - 18TH CEMENT PLASTER OUT SIDE AND 8TH CEMENT PLASTER INSIDE.
6. FLOORING - FLOORING IN PARKING AND URUBLE FLOORING IN ALL ROOMS.
7. DOORS & WINDOWS - T.W FRAME GLAZING WINDOW & VENTILATOR IN ALL ROOMS.
8. PAINTS - EXTERNAL PAINTS OF CEMENT PAINT.

SCHEDULE OF DOORS & WINDOWS

Sl. No.	TYPE	SIZE	DESCRIPTION
1	D	1050X2100	SINGLE LEAF WOODEN DOORS
2	DT	900X2100	DO
3	D	775X2100	DO
4	W	1800X200	PIVE LEAF GLAZED WINDOWS
5	W	1500X200	FOUR LEAF GLAZED WINDOWS
6	W	900X200	TWO LEAF GLAZED WINDOWS
7	V	900X200	CENTER HUNG VENTILATOR

AREA STATEMENT

PLOT AREA = 211.52 M
 ROAD W/AREA = 45.26 m
 NET PLOT AREA = 166.26 m
 GROUND FLOOR AREA = 94.60 M
 FIRST FLOOR AREA = 104.51 M
 TOTAL COVERD AREA = 199.11 M
 % OF GROUND COVERAGE = 44.72%
 F.A.R = 0.94

PROPOSED RESIDENTIAL BUILDING FOR
 SMT - SHASHI DEVI, W/O - SUKHRAM WUNDA
 AT - NH 33 NEAR BSNL OFFICE WUNDA COL
 BUNDU, PS+ PO BUNDU THANA N
 PLOT NO-60, KHATA NO-1116,

SHEET NO - 1



APPLICANT'S SIGNATURE