Project Title :SUJATA BARNWAL

















SPECIFICATIONS

1.BRICKWORK IN FOUNDATION & PLINTH SHALL BE OF FIRST CLASS BRICK IN CEMENTMORTAR 1:6 AND HALF BRICK WILL BE 1:4CEMENT MORTAR

2.MASONARY FOUNDATION WITH ISOLATED R.C.C COLUMN SHALL BE PROVIDED

3. CURTAIN GLAZING/ STTUCTURAL GLAZING OF GOOD QUALITY AND MARK VENTILATOR SYSTEM SHALL BE USED

4. ROLLING SHUTTER SHALL BE USED FOR SHOPS OPENINNGS

5. M.S GLAZED/ANODIZED ALUMINIUM/NCL SECCOLOR WINDOW AND R.C.C WITH CEMENT MORTOR 1:4

6. ALL R.C.C WORKS SHALL BE DONE IN 1:2:4 MIX CONCRETE

7. TATA TMT STEEL BARS SHALL BE USED IN R.C.C STRUCTURES COMMERCIAL QUALITY

8. ALL MASONARY SURFACE SHALL BE PLASTERED WITH CEMENT MORTAR 1:6 OVER R.C.C SLAB / P.C.C

9 ALLSTEEL AND WOOD WORK SHALL BE PAINTED WITH SYNTHETICENML.PAINT

10 ALL SANITARY AND ELECTRICAL FITTINGS SHALL BE OF STANDARD MARKAND WORKMENSHIP

11.KOTTA STONE / MOSAIC FLOORING INCLUDING STAIRCASE SALL BE USED

SL.NO. SCHEDULE OF OPENINGS

SI.NO.		SIZE	DESCRIPTION
1.	D	1.07X2.13	Sal wood chaukhat & Gamhar wood shutter
2.	D1	0.91X2.13	Sal wood chaukhat & Gamhar wood shutter
3.	D2	0.76X2.13	Sal wood chaukhat & Gamhar wood shutter
4.	W	1.52X1.52	Fully glazzed window
5.	W1	1.20X1.22	Fully glazzed window
6.	W2	0.91X1.22	Fully glazzed window
7.	V	0.61X0.61	CELLING VANTILOTER

SCHEDULE OF AREA

1. TOTAL PLOT AREA AS PER SITE : 242.66 SQM

2. PROPOSED AREA AT GROUND FLOOR :124.53 SQM

2. PROPOSED AREA AT FIRST FLOOR :124.53 SQM

3. TOTAL BUILD UP AREA : 249.06 SQM

4. COVERED AREA : $\frac{124.53X100}{242.66}$ = 51.32%

PROPOSED RESIDENTIAL BUILDING FOR
SMT - SUJATA BARNAWAL
W/O - SRI AJIT KUMAR
KHATA NO - 13 , PLOT NO -665
RAKWA.- 6.00 DISMIL.
THANA NO - 117.
MOHALLA - SALDEGA.
MAUZA - SALDEGA.
DISTT. - SIMDEGA (JHARKHAND)

RAJ ARCHITECT CONSULTANCY
CLUB COMPLEX ,GANDHI MAIDAN
MAIN ROAD SIMDEGA JHARKHAND
MOBILE - 094311-93425,093862-22833

SCALE - 1:100	SH.NO.
AS MENTIONED	1/1

SIGNATURE OF OWNER

Building :A (RESIDETAL)

SCHEDULE OF JOINERY:

SCHEDULE OF JOINERY:

UnitBUA Table for Building :A (RESIDETAL)