

NOTE:-

**SPECIFICATIONS**

- BRICKWORK IN FOUNDATION & PLINTH SHALL BE OF FIRST CLASS BRICK IN CEMENT MORTAR 1:6 AND HALF BRICK WILL BE 1:4 CEMENT MORTAR
- MASONRY FOUNDATION WITH ISOLATED R.C.C COLUMN SHALL BE PROVIDED
- CURTAIN GLAZING/ STRUCTURAL GLAZING OF VENTILATOR SYSTEM SHALL BE USED
- ROLLING SHUTTER SHALL BE USED FOR SHOPS FRONT
- M.S GLAZED/ANODIZED ALUMINIUM/NC R.C.C WITH CEMENT MORTAR 1:4
- ALL R.C.C WORKS SHALL BE DONE IN STARTING THE WORK
- TMT STEEL BARS (ØE 500) SHALL BE USED IN CONCRETE SHALL BE M-20 & shall be conforming to IS: 456 - 2000.
- ALL MASONRY SURFACE SHALL BE PLASTERED OVER R.C.C SLAB / P.C.C
- ALL STEEL AND WOOD WORK SHALL BE PAINTED WITH SYNTHETIC ENAMEL PAINT
- ALL SANITARY AND ELECTRICAL FITTINGS SHALL BE OF STANDARD MARK AND WORKMANSHIP
- KOTTA STONE / MOSAIC FLOORING INCLUDING STAIRCASE SHALL BE USED

SL.NO.	SCHEDULE OF OPENINGS	SIZE
1.	D	1.1X2.10
2.	D1	.90X2.10
3.	D2	.75X2.10
4.	W	1.50X1.20
5.	W1	1.20X1.20
6.	W2	.90X1.20
7.	V	.60X.60
8.	C.G	2.10X2.10

**SCHEDULE OF AREA**

1. TOTAL PLOT AREA AS PER SITE	: 242.40 SQ.M
2. PROPOSED AREA AT GROUND FLOOR	: 101.82 SQ.M
3. TOTAL BUILD UP AREA	: 101.82 SQ.M
4. COVERED AREA	: 101.82 X 100 = 10182.00 SQ.M

PROPOSED RESIDENTIAL BUILDING  
 MR - RAJNATH MANJHI  
 S/D - LATE SOMRA MANJHI  
 KHATA NO - 45 , PLOT NO -1162.  
 RAKWA.- 06 DISMIL.  
 THANA NO - 80.  
 MOHALLA -SALDEGA  
 MAUZA - SALDEGA  
 DISTT. - SIMDEGA (JHARKHAND)

**R.S CONSULTANT**  
 SONAR TOLI ,NEAR SAMLESHWARI TVS  
 MAIN ROAD SIMDEGA JHARKHAND  
 MOBILE - 7008039097

SCALE - 1:100 SH.NO.  
 AS MENTIONED 1/1

SIGNATURE OF LIC ENGINEER  
 NAGAR PARISHAD SIMDEGA

KHAATA NO:- 45  
 PLOT NO :- 1162  
 AREA :- 6 DECIMAL  
 THANA NO:- SIMDEGA  
 MAUZA :- SALDEGA  
 BOUNDARY:-  
 NORTH:- SAME PLOT  
 SOUTH:- 12' ROAD  
 EAST:- 12' ROAD  
 WEST:- SAME PLOT

CLIENT:- RAJNATH MANJHI  
 S/D:- LATE SOMRA MANJHI

NAME OF PROJECT :- Residential HOUSE PLAN

TITLE :- Submission plan

SHEET NO :-01 | SIMDEGA

