



BRIEF SPECIFICATION	
FOUNDATION-REINFORCED-CEMENT CONCRETE (1:1½:3)	
BRICK WORK IN FOUNDATION & SUPERSTRUCTURE	
FIRST CLASS BRICK WORK IN CEMENT MORTAR (1:6)	
D.P.C.-----1" D.P.C. IN CEMENT CONCRETE (1:2:4)	
FLOOR-----1" L.P.S. OVER 3" P.C.C.	
ROOF-----4" THK. R.C.C. ROOF (1:1½:3)	
LINTEL-----5" THK. R.C.C. LINTEL (1:1½:3)	
STAIRS-----RISE-6", TREAD-10"	
DETAILS OF AREA	
TOTAL LAND AREA (AS PER DEED)-	2160.00 S.Ft.
GROUND FLOOR AREA -----	1018.00 S.Ft.
FIRST FLOOR AREA -----	1018.00 S.Ft.
TOTAL COVERED AREA-----	2036.00 S.Ft.
% PLINTH AREA-----	47.13%
FAR-----	0.94
SCHEDULE	
D1 = 3'-6"X7'-0"	W1 = 5'-0"X4'-0"
D2 = 3'-3"X7'-0"	W2 = 4'-0"X4'-0"
D3 = 2'-6"X7'-0"	W3 = 3'-0"X4'-0"
GATE = 10'-0"X7'-0"	V = 2'-0"X2'-0"
TITLE OF DRAWING	
PLAN OF RESIDENTIAL BUILDING OF SMT MEENA DEVI, W/O SRI RAMDEV PRASAD, OF JAI PRAKASH NAGAR GALI NO - 04, DHANBAD, UNDER MOUZA- BHELATAND NO- 89, OLD KHATA NO- 22, NEW KHATA NO- 166, OLD PLOT NO- 2081, 2082, NEW PLOT NO- 1616, DIDD - DHANBAD, (JHARKHAND).	
SIGNATURE OF OWNER	
SIGNATURE OF ENGINEER	