







KEY PLAN

#### BRIEF SPECIFICATION

FOUNDATION:-R.C.C. (1:1.5:3) Column footing foundation
PLINTH:- 12"th R.C.C. (1:1.5:3) all round on plinth level.
FLOORING:- 1.5"th L.P.S. flooring over 3"th P.C.C. (1:3:6).
SUPER STRUCTURE:- First class brick work in cement mortar (1:6)

SLAB,BEAM & LINTEL :- All R.C.C. work (1:1.5:3).

WOOD WORK :- All door & window frames of sal wood.

PLASTERING: - 0.5"th cement plaster (1:6) both side.

SCHEDULE				
D- 1.000 x 2.100	W - 1.520 x 1.200			
D1- 0.900 x 2.100	W1- 1.200 x 1.200			
D2 - 0.750 x 2.100	W2- 0.900 x 1.200			
	V - 0.600 x 0.450			

#### DETAILS OF AREA

TOTAL AREA (AS PER DEED)	323.90	SqM.
TOTAL AREA (AS PER SITE)	323.46	SqM.
GROUND FLOOR AREA	176.27	SqM.
FIRST FLOOR AREA	246.50	SqM.
TOTAL COVERED AREA	422.77	SqM.
% OF PLINTH AREA	54.499	6
F.A.R	1.30	

## TITLE OF DRAWING

PROPOSED RESIDENTIAL BUILDING PLAN OF EZAZ, SO - EZHAR, RESIDENT OF QUIRTER NO. DAZSAG, NEAR RAILWAY CROSSING, JORAPOKHAR, MANJHALADH (#JAGBID, HITVALGORA, DIST. DHANBAD, HARKHAND, UNDER MOLZA-GAREDIYA, MOLZA NO. - 188, NEW KHATA NO. 73, OLD KHATA NO. - 35, NEW PLOT NO. - 49, OLD PLOT NO. - 281, TO HANBAD JIHAKHAND.

# SIG. OF OWNER

### SIG. OF ENGINEER

DRW. AT :-