



TITLE OF DRAWING

BRIEF SPECIFICATION

FOUNDATION-----CEMENT CONCRETE
 BRICK WORK IN FOUNDATION & SUPERSTRUCTURE
 FIRST CLASS BRICK WORK IN CEMENT MDR.(1:6)
 D.P.C.----1" D.P.C. IN CEMENT CON. (1:2:4)
 FLOOR-----1" I.P.S. OVER 3" P.C.C.
 ROOF-----4"THK. R.C.C. ROOF (1:1.5:3)
 LINTEL-----6"THK. R.C.C. LINTEL (1:1.5:3)
 STAIRS-----RISE---7", TREAD--- 10"
 DOORS-----D-3'3"x7'0" D1-3'0"x7'0", D2-2'6"x7'0"
 WINDOWS-----W-4'0"x4'0", W1-3'0"x4'0"
 VENTS-----V-2'0"x2'0"

STATEMENT OF AREA

TOTAL PLOT AREA- 202.41 SQM.
 LEFT FOR ROAD AREA- 27.64 SQM.
 NET PLOT AREA- - 174.77 SQM.
 GROUND FLOOR AREA- 114.53 SQM
 FIRST FLOOR AREA- - 114.53 SQM.
 TOTAL COV. AREA- 229.06 SQM.
 % OF COV.- 65.53%
 F.A.R. 1.311

OWNER

ENGINEER